BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/10/2020-21 Dated: 23-02-2021

APPROVED TENDER SCHEDULE –'B'

Item 06

Name of Work :-Additional and alteration of Govt School at Ananthapura village in Attur ward No 03

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri LAKSHMAN P	
				Rate	Rate in Words
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the exavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods Complete as per specifications and the directions of the Engineer-in-charge	Cum	196.56	484.92	Four Hundred EightyFour Paise NinetyTwo Only
2	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. Complete as per specifications and the directions of the Engineer-in-charge	Cum	14.62	2623.32	Two Thousand Six Hundred TwentyThree Paise ThirtyTwo Only
3	Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing Complete as per specifications and the directions of the Engineer-in-charge	Cum	31.04	5510.16	Five Thousand Five Hundred Ten Paise Sixteen Only

	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Complete as per specifications and the directions of the Engineer-in-charge	Cum	31.18	5754.24	Five Thousand Seven Hundred FiftyFour Paise TwentyFour Only
5	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerddressed in courses not less than 20 cms high, bond stones at 2m apart in each course including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Cum	46.15	4963.68	Four Thousand Nine Hundred SixtyThree Paise SixtyEight Only
6	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing Complete as per specifications and the directions of the Engineer-in-charge	Cum	10.56	6485.40	Six Thousand Four Hundred EightyFive Paise Fourty Only
7	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Sqm	23.46	153.36	One Hundred FiftyThree Paise ThirtySix Only
8	Filling available excavated earth(excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour Complete as per specifications and the directions of the Engineer-in-charge	Cum	51.16	217.08	Two Hundred Seventeen Paise Eight Only
9	Conveying the excavated earth, debries etc., with all lead and lifts including loading and unloading charges etc., Complete as per specifications and the directions of the Engineer-in-charge	Cum	145.40	67.09	SixtySeven Paise Nine Only

	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	75.24	278.64	Two Hundred SeventyEight Paise SixtyFour Only
11	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness , including attached pilasters, buttresses, plinth and string courses cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	90.72	386.64	Three Hundred EightySix Paise SixtyFour Only
12	Providing and removing centering, shuttering, strutting, propping etc. and Removal of form Work for columns, pillars, piers, post and struts, square / rectangular / polygon in plan including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	65.70	492.48	Four Hundred NinetyTwo Paise FourtyEight Only
13	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons for heights more than 3.50m from ground level. - 0 to 5 mtrs. Complete as per specifications and the directions of the Engineer-in-charge	Sqm	156.42	432.00	Four Hundred ThirtyTwo Only
14	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	8.31	815.40	Eight Hundred Fifteen Paise Fourty Only
15	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	110.52	315.36	Three Hundred Fifteen Paise ThirtySix Only
16	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	1.89	561.60	Five Hundred SixtyOne Paise Sixty Only

	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc. , including edges including cost of all materials, labour Complete as per specifications and the directions of the Engineer-in-charge	Sqm	7.02	348.84	Three Hundred FourtyEight Paise EightyFour Only
18	Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement complete as per specifications and the directions of the Engineer-in-charge	Cum	68.25	6276.96	Six Thousand Two Hundred SeventySix Paise NinetySix Only
19	Providing and laying in position reinforced cementconcrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum andfine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated fo all works in ground Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck ness) including attached plasters ,columns, pillars,posts,struts.butters,string or lacing courses ,parapets,coping,bed blocks,anchor blocks ,plain window cills,fillets including cost of all materials, labour,HOM of machinery, curing, Complete as per specifications and the directions of the Engineer-in-charge	Cum	6.38	6528.60	Six Thousand Five Hundred TwentyEight Paise Sixty Only

	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C.C works laid in 15 cms thick layers and well compacted including vibrating, curing, etc for all super Structure works with all lead and Lift etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed cement for concrete with M-25 complete as per specifications and the directions of the Engineer-in-charge	Cum	37.15	5936.76	Five Thousand Nine Hundred ThirtySix Paise SeventySix Only
21	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, . Complete as per specifications and the directions of the Engineer-in-charge	Sqm	5.40	535.68	Five Hundred ThirtyFive Paise SixtyEight Only
22	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specifications and the directions of the Engineer-in-charge	tonne	14.46	84247.56	EightyFour Thousand Two Hundred FourtySeven Paise FiftySix Only
23	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., Complete as per specifications and the directions of the Engineer-in-charge	Sqm	274.47	984.96	Nine Hundred EightyFour Paise NinetySix Only

	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Sqm	423.21	281.88	Two Hundred EightyOne Paise EightyEight Only
25	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Sqm	10.83	221.40	Two Hundred TwentyOne Paise Fourty Only
26	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Sqm	227.49	220.32	Two Hundred Twenty Paise ThirtyTwo Only
27	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to ceiling including rounding off corners wherever required smooth rendering, : including Providing and removing scaffolding, including cost of materials, labour, curing Complete as per specifications and the directions of the Engineer-in-charge	Sqm	178.80	243.00	Two Hundred FourtyThree Only
28	Providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty . Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of alll mateerial cost of labour and scaffolding etc. , Complete as per specifications and the directions of the Engineer-in-charge	Sqm	406.29	84.24	EightyFour Paise TwentyFour Only
29	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, Complete as per specifications and the directions of the Engineer-in-charge	Sqm	227.49	97.20	NinetySeven Paise Twenty Only

	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications Extra over for applying oil bound washable distemper on ceiling and / or sloping roof Complete as per specifications and the directions of the Engineer-in-charge	Sqm	178.80	127.44	One Hundred TwentySeven Paise FourtyFour Only
31	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, - with primer. Complete as per specifications and the directions of the Engineer-in-charge	Sqm	423.21	110.16	One Hundred Ten Paise Sixteen Only
32	Providing and laying M-15 cement concrete flooring, 50 mm thick with metallic concrete hardner topping , under layer of 35mm thick m-15 cement concrete using broken granite metal of 20mm and down size, and top layer 50mm thick of metallic cement hardner consisting of mix 1:2 (1 cement hardner mix : 2 granite metal 10mm nominal size) by volume, with which metallic hardening compound of approved quality mix in the ratio of 4:1 (4 part of cement and 1 part of metallic floor hardening compound of approved quality by wt) , including finishing cost of materials, labour, curing, Complete as per specifications and the directions of the Engineer-in-charge	Sqm	143.70	681.48	Six Hundred EightyOne Paise FourtyEight Only
33	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli gray granite in CM 1:4 proportion, cut to required shape, pattern with paper joints, finished with cement mortar using white cement and colour pigments to match the colour of slab making through jointing with sealant, groves in joints including cost of curing - minimum width of 900mm.Complete as per specifications and the directions of the Engineer-in-charge	Sqm	154.53	2137.32	Two Thousand One Hundred ThirtySeven Paise ThirtyTwo Only

	Providing half nosing for 20mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., Complete as per specifications and the directions of the Engineer-in-charge	m	72.20	194.40	One Hundred NinetyFour Paise Fourty Only
35	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all Complete as per specifications and the directions of the Engineer-in-charge	Sqm	156.42	568.08	Five Hundred SixtyEight Paise Eight Only
36	Fixing of door frames in an existing opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, Complete as per specifications and the directions of the Engineer-in-charge	Nos	3.00	1475.28	One Thousand Four Hundred SeventyFive Paise TwentyEight Only
37	Providing Honne wood frames of doors, windows, clerestory windows,ventilators and other frames , wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps),but including cost of materials, labour, HOM of machineries Complete as per specifications and the directions of the Engineer-in-charge	Cum	0.37	94612.32	NinetyFour Thousand Six Hundred Twelve Paise ThirtyTwo Only

	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per specifications and the directions of the Engineer-in-charge	Sqm	7.56	5099.76	Five Thousand NinetyNine Paise SeventySix Only
39	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost ofmaterials, labour, Complete as per specifications and the directions of the Engineer-in-charge	Sqm	7.56	104.76	One Hundred Four Paise SeventySix Only
40	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick, weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mmx18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws, raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar using aluminium	Sqm	20.25	4789.80	Four Thousand Seven Hundred EightyNine Paise Eighty Only
41	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approve design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machineryComplete as per specifications and the directions of the Engineer-in-charge	Kg	425.25	102.60	One Hundred Two Paise Sixty Only

	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, Complete as per specifications and the directions of the Engineer-in-charge	sqm	40.50	102.60	One Hundred Two Paise Sixty Only
43	Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) MORTH Complete as per specifications and the directions of the Engineer-in-charge	Cum	78.84	351.00	Three Hundred FiftyOne Only
44	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members asshown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., Complete as per specifications and the directions of the Engineer-in-charge	Sqm	11.34	3252.96	Three Thousand Two Hundred FiftyTwo Paise NinetySix Only
45	Dismantling of barbed wire fencing / wire mesh fencing including posts, foundation concrete, back filling of pit by manual means including disposal of dismantled material with all lifts and stacking serviceable material and unserviceable material separately Complete as per specifications and the directions of the Engineer-in-charge	m	35.20	71.28	SeventyOne Paise TwentyEight Only

	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Netural) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper confirming to the GTP With a 6Amps flusg type SP control switch shall be fixed on the existing plastic sheet / gand box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block, Complete as per specifications and the directions of the Engineer-in-charge t. Short point upto 3m	Point	7.00	200.00	Two Hundred Only
47	Point wiring using copper wire without switch (Class A material). Supplying and wiring adopting loop system in existing PVC conduit/casing capping using 2X1.5Sqmm(phase &Netural) &1X1.0 Sqmm (Earth Wire) FRLSmultistrand PVC insulated ,2x1.5sqmm copper confirming to the GTP With a 6Amps flusg type SP control switch shall be fixed on the existing plastic sheet / gand box .the other end of the wire shall be terminated with sufficient loose length in a wood/PVC round block,Complete as per specifications and the directions of the Engineer-in-charge . Medium point above 3m - 6m	Point	8.00	275.00	Two Hundred SeventyFive Only
48	Concealed Conduit System - Supplying heavy gague PVC conduit pipe 20/25/32 mm dia 2mm thick confirming to IS 2509 with suitable size bends metal/pvc junction boxes, adhesive paste etc, and running before concreting and slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fisg wire wherever necessary 25mm dia, 2mm thick Complete as per specifications and the directions of the Engineer-in-charge	Rm	30.00	53.00	FiftyThree Only
49	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary. 19/20mm dia, 2mm thick Complete as per specifications and the directions of the Engineer-in-charge	Rm	25.00	51.00	FiftyOne Only

	Groove cutting : Supplying heavy gauge conduit PVC 25/2mm of s thick heavy with suitable size bend , metal junction boxes, adhesive pastes etc, by groove cutting in a wall and fixing by bracing U or J hooks and cement plastering up to the surface and run with 18SWG GI fish wire run throughout the conduit where ever necessary.25mm dia, 2mm thick Complete as per specifications and the directions of the Engineer-in-charge	Rm	15.00	54.00	FiftyFour Only
51	Supplying and flush modular poweder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall 1 - 3 Way Complete as per specifications and the directions of the Engineer-in-charge	Each	5.00	95.00	NinetyFive Only
52	Supplying and flush modular poweder coated / galvanized metal box suitable for mounting modular switch plates. the box should be firmil flush mounted after due groove cutting in brick /stone/C.C wall 4 - 5 Way Complete as per specifications and the directions of the Engineer-in-charge	Each	6.00	105.00	One Hundred Five Only
53	Supplying 6A flush type socket and 6 amp flush type SP switch either surface/flush mountinh in existing gang box or in 4mm thik plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wire as required as per IS 1293 and IS 3654 . 6AMP 3/5 and Switch Complete as per specifications and the directions of the Engineer-in-charge	No	3.00	132.00	One Hundred ThirtyTwo Only
54	Supplying and mounting 2 Nos, of 2 Way 6amps flush type switches either surface/flush mounted on existing gang box or in 4mm thick plastic sheet and mounted on a flusg mounted wooden box and wiring as per IS 1293 Complete as per specifications and the directions of the Engineer-in-charge	Each	3.00	150.00	One Hundred Fifty Only
55	Supply and fixing of bakelite D.P /socket/switch with/ without neon indicator over existing wood board or flush mounting in plastic plates/nitches as per IS 1293 and IS 3854 16Amps Combined switch and socket with indication Complete as per specifications and the directions of the Engineer-in-charge	No	3.00	194.00	One Hundred NinetyFour Only
56	Electronic stepped regulator. Complete as per specifications and the directions of the Engineer-in-charge	No	2.00	150.00	One Hundred Fifty Only

	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements. 1.5sqmm Complete as per specifications and the directions of the Engineer-in-charge	Rm	30.00	20.05	Twenty Paise Five Only
58	Wiring for lighting/power circuit using Grade using one of FRLS PVC insulated 1100 volts grade, multistrand copper with low conductor resistance single core wire in open or concealed system of wiring. With specified IS-694: confirming to Latest amendements. 2.5sqmm Complete as per specifications and the directions of the Engineer-in-charge	Rm	30.00	32.00	ThirtyTwo Only
59	Supplying and fixing Metal Fan Box with Round Hook Complete as per specifications and the directions of the Engineer-in-charge	Each	3.00	85.00	EightyFive Only
60	Suppiying and fixing of slim box Fitting ,made out of CRCA sheet metal body with locking type holder completely wired Excluding Ballast &Flouresent Tube. 1X4' Tube light Fitting Complete as per specifications and the directions of the Engineer-in-charge	Nos	4.00	300.00	Three Hundred Only
61	Supplying capacitor type ceiling fan complete with down rod blades shackle, canopies etc, for operation on 230 volts, 50 cycles. single phase AC supply conforming to ISS-374-1979 and with double ball bearing system Complete as per specifications and the directions of the Engineer-in-charge	Each	3.00	2090.00	Two Thousand Ninety Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.